# Project management for the construction of entertainment venue

# Table of Contents

Introduction	3
Work breakdown structure (WBS)	3
Project plan	5
Network diagram.	7
Budget and cost analysis	9
Risk analysis	13
	16
	10

#### Introduction

The objective of this report is to develop a project plan to construct an entertainment venue at Viharamahadevi Park. The venue will include a stage, seating for 100 people, a catering stall and a ticketing booth. The venue will be in place for 16 days from  $12-28^{th}$  July 2019. Project will start  $3^{rd}$  July onward. This project only consider about construction and maintenance of venue but not considering organize the event. This project plan includes Gantt chart, network diagram, cost estimate and risk analysis. Total project time of the project is 27 days and within the project period weekends are also considered as working days.

#### Work breakdown structure (WBS).

Work Breakdown Structure (WBS) is the hierarchical decomposition of the entire project and it is used to split the overall project into different tasks. WBS help to project team to allocate resources, funds, time and responsibilities, and review the progress of each project tasks (Khohil and Chitkara, 2008). Furthermore, project team can take speed corrective actions if the WBS plan is delayed or changed.





## **Project plan**

Detailed project plan has been conducted in below MS project document.



Gantt chart, work breakdown structure, resource usage, task usage, resource sheet any many other aspects of the project have been conducted in the project plan. Gantt chart is a type of bar chart which show the detail project schedule. Further, resources and cost can be allocated to different project tasks based on the Gantt chart via MS project. Gantt chart of the Entertainment venue project can be referred in above MS project document. Task based costs and resources are also entered in to Gantt chart.

# Figure 02 – Screenshot of Gantt chart.

ID	0	Task Mode	Task Name	Duration	Start	Finish	Finish Slack	Predecessors	Resource Names n 3	30, 19   Jul 7, 19   Jul 74, 79   Jul 21, 19   Jul 25, 19   Aug 4, 19   Aug 11, 19   It with tels shut thin tels shut tel
0		-	Construction of entertainment venue	27 days	Wed 7/3/19	Mon 7/29/19	0 days			
1		-	Planning	2 days	Wed 7/3/19	Thu 7/4/19	0 days			
2		-	Conduct a site visit to identify construction requirements	s 1 day	Wed 7/3/19	Wed 7/3/19	0 days		Project manager,Designer	Project manager,Designer
3		-	Design the venue	1 day	Thu 7/4/19	Thu 7/4/19	0 days	2	Designer	-Decigner
4		-	Medical facility	27 days	Wed 7/3/19	Mon 7/29/19	0 days			
5		-	Supply medical requirements	1 day	Wed 7/3/19	Wed 7/3/19	0 days		Medicines and equipment[1],Medic	Medicines and equipment(1),Medical team
6	127	-	Provide medical facilities	26 days	Thu 7/4/19	Mon 7/29/19	0 days	5	Medical team	Medical team
7		-	Power supply	2 days	Wed 7/3/19	Thu 7/4/19	1 day		1.1	
8		-	Get the generator	1 day	Wed 7/3/19	Wed 7/3/19	1 day		Generator [1], procurement team r	Generator [1], procurement team member 1
9		-	Arrange the power supply	1 day	Thu 7/4/19	Thu 7/4/19	1 day	8	Fuel (20), Electrician	Euch [20], Electrician
10		-	Seating	3 days	Fri 7/5/19	Sun 7/7/19	21 days			
11	-	-	Order and supply seats and other equipment	2 days	Fri 7/5/19	Sat 7/6/19	21 days	3	procurement team member 1	procurement team member 1
12		-	Arrange seats	1 day	Sun 7/7/19	Sun 7/7/19	21 days	11	seats[100], supporting team 1	seats[100], supporting team 1
13		-	Stage	4 days	Fri 7/5/19	Mon 7/8/19	0 days	3		
14	-	-	Order and supply components to buildup the stage.	1 day	Fri 7/5/19	Fri 7/5/19	D days	3	components of stage[1], Procureme	components of stage[1], Procurement team member 2
15		-	Buildup the stage	3 days	Sat 7/6/19	Mon 7/8/19	0 days	14,9	Construction team	Construction team
16	-	-	Catering stall	4 days	Fri 7/5/19	Mon 7/8/19	21 days			
17	-	-	Order the components for catering stall	1 day	Fri 7/5/19	Fri 7/5/19	23 days	3	Procurement team member 3(50%)	-Recurement team member 3(50%),components of cate(ing stall[1]
18	-	-	Buildup the catering stall	1 day	Mon 7/8/19	Mon 7/8/19	21 days	17.12	supporting team 1	supporting team 1
19		-	Ticketing booth	4 days	Fri 7/5/19	Mon 7/8/19	21 days			
20	-	-	Order and supply components for ticketing booth	1 day	Fri 7/5/19	Fri 7/5/19	23 days	3	components of ticketing booth[1].P	components of ticketing booth[1],Procurement team member 3[50%]
21	-	-	Buildup the ticketing booth	1 day	Mon 7/8/19	Mon 7/8/19	21 days	20.12	Supporting team 2	Supporting team 2
22	-	-	Fence	3 days	Tue 7/9/19	Thu 7/11/19	18 days			
23	-	-	Order and supply components for fance	1 day	Tue 7/9/19	Tue 7/9/19	18 days	3FS+4 days	Procurement team member 2 Com	-Procurement team member 2. Components for fence [1]
24	12 1	-	Buildup the fence	1 day	Thu 7/11/19	Thu 7/11/19	18 days	73FS+1 day	supporting team 1	supporting team 1
25		-	Decoration	2 days	Tue 7/9/19	Thu 7/11/19	18 days			
26	-	-	Stage decoration	2 days	Tue 7/9/19	Wed 7/10/19	D days	15	Stage decoration items[1] Designer	Stage decoration items[1] Designer
27	-	-	Other decorations	2 days	Wed 7/10/19	Thu 7/11/19	18 days		Other decoration items[1] Sunnort	Other decoration items[1] Supporting team 2
28		-	Lighting	Adaus	Sun 7/7/19	Wed 7/10/19	0 days		Count Bern Bran Januar Prakhas a	
20	-	-	Supply lighting aquinment	2 daur	Sup 7/7/19	Mon 7/8/19	D days	255+2 dave	Procurement team member 2150%	Programment team member 3(50%) stage lights [5] other lights [10]
30	-	-	Arrange lighting	2 days	Tue 7/9/19	Wed 7/10/19	D days	29 15 2655	Electrician (50%) technician 1	Electrician 50% Ltechnician 1
21	-	-	Sounds	Adaus	Sun 7/7/10	Wed 7/10/10	0 days	23,23,2033	checken googleterment r	
31	123		Supply could equipment	2 days	Sun 7/7/19	Mon 7/8/19	D days		Speakers (4) Microsphere (2) Procure	Speakers(4) Microphone(2) Procurement team member 3/50%)
32	123	-	Setup round	2 days	Tue 7/9/19	Wed 7/10/19	D days	22.15	technician 2 Electrician(50%)	technician 2. Electrician (50%)
24	1973	-	Charle sound and links	1 4 4 4	The 7/11/10	Thu 7/11/10	O days	30,23	technician 2 technician 1	technician 2 technician 1
34	123	-	Cleaning and light	1 day	Thu //11/19	Mag 7/14/19	D days	30,33	Cleaning team Biar(1) cleaning equi	Cleaning team Bins[5] cleaning equipme
35		-	Event	17 days	5-1 7/12/10	Sun 3/39/10	O days		Ceaning ream, and streaming edge	
30	-	-	Event	17 days	FT 7/12/19	54 7/12/19	18 days	18 21 24 27 2		÷ .
3/		<u> </u>	Start the event	U days	Fit 7/12/19	Fin 7/12/13	Le Gays	10,21,24,27,3	technician 1 technician 3 Funneatin	the building 1 technician 2 Supporting team
30	100	-	Find the super-	17 days	Fn //12/19	Sun 7/28/19	0 days	3/35	technician 1,technician 2,supportin	
39	172	2	End the event	1 days	Sun //28/19	Sun 7/28/19	D days	3077	Courte attention averaging the	A construction team supportion team 1
-	1.5	-+	Withdraw the venue	TOAY	Mon 7/29/19	Mon 7/29/19	D days	3577,39	construction team ,supporting team	Construction stam , apporting stam 2
			Task	nactive Task			Manual Summ	ary Rollup 💼	External Milestone	Manual Progress
			Split Ir	nactive Mile	stone		Manual Summ	ary F	Deadline	•
Proje	ect: Cons	truction of	fentertain Milestone	naction Sur	mary I	1	Start-only	C	Critical	
Date	- Pri 10/4	419		and and			Field		Contraction of the second	
			summary	nariual Task			Finish-only	-	Critical Split	A DECIDENT DECIDENTS
			Project Summary D	uration-on	ly in		External Tasks		Progress	
								Page 1		

### Network diagram.

Network diagram is the one of commonly used project planning technique that help to complete the project within shortest possible time (Sivaganathan, 2008). Total time that need to be allocated to complete this project is 792 man hours. However, as a team, project team need to complete the project within 27 days. Therefore, Network diagram is highly important for time management. Further, it clearly illustrate the critical task that project team need to complete within the time schedule.

Screenshot of this project network diagram is attached below and clear network diagram can be referred in MS project document. Critical path of the project is shown in red in network diagram. Please refer the network diagram in below link.



Figure 02 – Screenshot of network diagram.



#### **Budget and cost analysis**

The main objective of the cost planning process is to identify the importance cost factors and identify the potential for compromise the cost within different components of the project. For the cost analysis of this project, a bottom-up approach has been used. Bottom-up estimates of the each level in the WBS are added from each level of the project hierarchy (Maylor, 2006). Estimate cost of this project is Rs 777,650.00. Further, these calculated costs have been considered as baseline costs of the project.

Resource Name	Туре	Material Label	Initials	Group	Max. Units	Std. Rate	Ovt. Rate	Cost/Use	Accrue At	Base Calendar
Designer	Work		Designer		100%	Rs. 625.00/hr	Rs. 0.00/hr	Rs. 0.00	Start	Standard
Project manager	Work		PM		100%	Rs. 0.00/hr	Rs. 0.00/hr	Rs. 27,000.00	End	Standard
procurement team member 1	Work		Procure 1		100%	Rs. 250.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Procurement team member 2	Work		Procure 2		100%	Rs. 250.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Medical team	Work		Medical		100%	Rs. 250.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Cleaning team	Work		СТ		100%	Rs. 200.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Medicines and equipment	Materia		Medicines			Rs. 0.00		Rs. 7,000.00	Start	
Generator	Materia		Generator			Rs. 50,000.00		Rs. 10,000.00	Start	
Fuel	Materia	L	Fuel			Rs. 100.00		Rs. 1,000.00	Start	
Electrician	Work		Electrician		100%	Rs. 250.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Procurement team member 3	Work		Procure 3		100%	Rs. 250.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
seats	Materia		Seats			Rs. 300.00		Rs. 5,000.00	Start	
supporting team 1	Work		Suporting team 1		100%	Rs. 1,000.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard

#### Table 01 – Resource sheet

components of stage	Material		Stage components		Rs. 0.00		Rs. 75,000.00	Start	
Construction team	Work	c t	construction team	100%	Rs. 1,500.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
components of catering stall	Material	(	Catering stall Components		Rs. 0.00		Rs. 25,000.00	Start	
components of ticketing booth	Material	-   (	Ticketing booth components		Rs. 0.00		Rs. 7,000.00	Start	
Supporting team 2	Work	: 1	Supporting team 2	100%	Rs. 1,000.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Components for fence	Material	l	Fence components		Rs. 0.00		Rs. 20,000.00	Start	
Stage decoration items	Material	Ş	stage deco		Rs. 0.00		Rs. 22,000.00	Start	
Other decoration items	Material	(	other deco		Rs. 0.00		Rs. 17,000.00	Start	
stage lights	Material	e s	Stage lights		Rs. 7,000.00		Rs. 5,000.00	Start	
other lights	Material		other lights		Rs. 1,000.00		Rs. 0.00	Start	
technician 1	Work	t	tech 1	100%	Rs. 300.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
technician 2	Work	t	tech 2	100%	Rs. 300.00/hr	Rs. 0.00/hr	Rs. 0.00	Prorated	Standard
Speakers	Material	Ş	speakers		Rs. 5,000.00		Rs. 0.00	Start	
Microphone	Material	1	Mic		Rs. 3,000.00		Rs. 0.00	Start	
Bins	Material	ł	bins		Rs. 150.00		Rs. 0.00	Start	
cleaning equipment	Material	(	cleaning equipment		Rs. 100.00		Rs. 0.00	Start	

# Cost baseline.

Follow the below link to refer cost baseline.



The cost baseline refer the amount of money which is predicted to cost for the project. This is useful to identify the actual performance deviation from the expected plan.

# Table 02 – cost estimate

Task Name	Total Cost
Conduct a site visit to identify construction requirements	Rs. 32,000.00
Design the venue	Rs. 5,000.00
Planning	Rs. 37,000.00
Supply medical requirements	Rs. 9,000.00
Provide medical facilities	Rs. 52,000.00
Medical facility	Rs. 61,000.00
Get the generator	Rs. 62,000.00
Arrange the power supply	Rs. 5,000.00
Power supply	Rs. 67,000.00
Order and supply seats and other equipment	Rs. 4,000.00
Arrange seats	Rs. 43,000.00
Seating	Rs. 47,000.00
Order and supply components to buildup the stage.	Rs. 77,000.00
Buildup the stage	Rs. 36,000.00
Stage	Rs. 113,000.00
Order the components for catering stall	Rs. 26,000.00
Buildup the catering stall	Rs. 8,000.00
Catering stall	Rs. 34,000.00
Order and supply components for ticketing booth	Rs. 8,000.00
Buildup the ticketing booth	Rs. 8,000.00
Ticketing booth	Rs. 16,000.00
Order and supply components for fence	Rs. 22,000.00
Buildup the fence	Rs. 8,000.00
Fence	Rs. 30,000.00
Stage decoration	Rs. 32,000.00
Other decorations	Rs. 33,000.00
Decoration	Rs. 65,000.00
Supply lighting equipment	Rs. 52,000.00
Arrange lighting	Rs. 6,800.00
Lighting	Rs. 58,800.00
Supply sound equipment	Rs. 28,000.00
Setup sound	Rs. 6,800.00
Sounds	Rs. 34,800.00
Check sound and light	Rs. 4,800.00
Cleaning	Rs. 39,650.00
Start the event	Rs. 0.00
Maintenance	Rs. 149,600.00
End the event	Rs. 0.00
Event	<b>Rs. 149.600.00</b>
Withdraw the venue	Rs. 20,000.00
Construction of entertainment venue	<b>Rs. 777,650.00</b>

## **Risk analysis**

Main risks of the project have been identified below and suitable risk mitigation actions are also suggested.

Table 03 – Risk as	ssessment
--------------------	-----------

Ref. no.	Risk	Impact	Likelihoo d	Risk mitigating action plans
1	Security threat	Major	Unlikely	Inform the police and provide security for the event.
2	Interrupt due to bad weather	Moderate	Likely	Check the weather updates, Provide suitable covers, Clear the draining system.
3	Accidents in the work place	Major	Likely	Provide pre training for employees. Provide and use safety equipment. Ensure medical team available in all the time. Getting insurance
4	Absence of key employees	Moderate	Moderate	Hire employees from third party.
5	Delays in supply components	Moderate	Likely	Communicate with procurement team frequently. Place order on time and coordinate with suppliers.
6	Constructions is not going according to design.	Major	Unlikely	Coordinate with designer frequently.
7	Interruption due to power cut.	Moderate	Likely	Use generator.
8	Unexpected increase of equipment cost	Moderate.	Likely	Keep additional budget.

Risk register need to be updated by including all possible risks. Associated risk can be identified based on the previous experiences, different internal and external sources, key risk symptoms or performing time, cost, quality analysis (Baker and Cole, 2012). There need to be proper criteria to measure impact and likelihood. By having proper project plan, many associated risks can be mitigated.

# Table 05 – risk ratings

<b>Risk Rating</b>	What it Means
E Extreme	<ul> <li>Project sponsor's attention is required.</li> <li>Immediate actions need to be taken by higher management with a detailed research and management risk treatment plan.</li> </ul>
H High	<ul> <li>Project sponsor's attention is required.</li> <li>Risk must be managed by project sponsor and project manager with a detailed risk treatment plan.</li> </ul>
S Significant	<ul> <li>Project manager's attention is required.</li> <li>Project manager responsibility specified.</li> <li>Risks should be treated using one or more of the risk treatment options</li> </ul>
M Moderate	<ul> <li>Risks need to be treated using one or more of the risk treatment options</li> <li>Risks need to be managed using specific monitoring or treatment processes.</li> </ul>
L Low	<ul> <li>Risk is accepted with minimal treatment and can generally be managed using existing routine procedures.</li> <li>Low risks need to be monitored and constantly reviewed to ensure they remain acceptable.</li> </ul>





## References

Maylor, H. (2006). Project Management (3rd ed.). India: Pearson Education

Sivaganathan, A. (2016). *Lecture Notes: Project Management*, Colombo: Postgraduate Institute of Management

Kohil, U., & Chitkara, K.K.(2008). *Project Management Handbook* New Delhi: Tata McGraw – Hill Publishing Company Ltd

Barker, S., & Cole, R.(2012). *Brilliant Project Management: what the best project managers know, do, and say* (3<sup>rd</sup> ed.). London: Pearson Education